

Price Bid- B4 Package Sewage Treatment Plant having capacity of 80KLD					
Sr. No.	Description	Qty	Per	Rate	Amount
1	<p><b>80 KLD MBBR (Moving Bed Bio Reactor) Package -</b>            Designing (hydraulic, process, structural and aesthetic), providing, construction, hydraulic testing, commissioning and giving satisfactorily trial run for 3 months of STP consisting of Inlet Chamber, Screen chamber, Grit Separator, Redy Package MBBR (Based on technologies providing attached growth on plastic media kept suspended in the sewage due to low density of plastic and provided with diffused air for aeration with tank, Secondary Clarifier, Sludge collection sump, Gravity Sludge Thickener, Chlorine Contact Tank, Chlorinator room, Sludge Dewatering Equipment, associated piping work with required valves, gates, drains, Administration Block cum Laboratory, associated buildings, Laboratory Equipments, inclusive of mandatory spare parts and instrumentation, etc.complete as turnkey job with all involved civil, electrical, instrumentation and mechanical works inclusive of all items, units as per detailed specifications for civil, electrical, instrumentation and mechanical components with all duties, Transportation, erection and taxes etc. complete to achieve BOD &lt; 10ppm, TSS &lt; 10ppm, Biological TN &lt; 10ppm &amp; PO4 &lt; 2ppm to get recyclable quality of water for industrial / agricultural purposes. all inlate and out late Pipe connection and one year warranty including in the package Min. freeboard of 0.3m shall be maintained unless otherwise asked for 0.5m stipulated for specific units.</p>	1	JOB	0.00	0.00
<b>Total Cost of STP</b>				<b>Rs.</b>	