

## Draft Tender

Tender No- 25/Umarsar/Civil/20-21

**Name of work- -:** Renovation of existing old time office bldg at Umarsar Lignite mines,  
taluka- Lakhpat, Dist- Kutch

**Issued To**

.....  
.....  
.....Pin no.....

**GUJARAT MINERAL DEVELOPMENT CORPORATION LTD**  
(A Government of Gujarat Enterprise)  
Lignite Project Umarsar, Post- Ghaduli  
Taluka- Lakhpat, Dist- Kutch. Pin code- 370627

The local tender committee has examined the terms & conditions of the tender and found it proper for go ahead with the process.

Submitted for approval of G.M(Project).

*13.01.06/01*  
J E (Civil)

*[Signature]*  
DGM(Safety)

*[Signature]*  
G.M(Project)  
Umarsar

*[Signature]*  
A.M(H.R)

**GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED**

( A Government of Gujarat Enterprise )

**Lignite Project, Umarsar, P.O: S.K.V.Nagar Pin- 370601**Tal: Lakhapat, Dist: Kutch (GUJ) E mail: [umarsar@gmdcltd.com](mailto:umarsar@gmdcltd.com)

PHONE: + (02839) 293693 FAX: + (02839) 294428 CIN:L14100GJ1963SFC001206

**Tender No- 25/ Umarsar / Civil /20-21.****Name of Work-:** Renovation of existing old time office bldg at Umarsar Lignite mines,  
taluka- Lakhpat,Dist- Kutch.


<b>01</b>	<b>Tender No</b>	<b>25/civil/Umarsar/20-21</b>
02	Location	G.M.D.C Ltd, Umarsar Lignite Project,Taluka-Lakhpat,Dist-Kutch
03	Work completion time	45 days
04	Issue and Last date of issue of inquiry	From Dt.13/01/2021 to 25/01/2021 Up to 05:00 P.M
05	Last date of submission of tender	26/01/2021 Up to 05:00 P.M
06	Date and time of opening of tender	27/01/2021 at 08:00 A.M
07	Tender Fee(Non refundable)	Demand draft of Rs.500/- Plus 18% GST( <b>Rs.590/-</b> ) of any Nationalized/schedule bank (except co-operative bank) In Favor of " <b>GMDC Ltd</b> " payable at <b>Umarsar</b>
08	EMD(Earnest Money Deposit)	Demand draft (D.D) of Rs.2856/- any Nationalised bank/schedule bank (except co-operative bank) only in favor of " <b>GMDC Ltd</b> " payable at <b>Umarsar</b> . Cheques or bank guarantee will not be accepted.
09	Security Deposit	5% of tender Amount
10	Defect liability period	12 months (01 years) after Completion of work
07	Validity of tender	90 days
08	Term of payment	100% payment will be made by project.
09	Estimated cost	Rs.2,85,591/-(excluding GST)

Corporation reserves the rights to reject any or all tender or part thereof or split the work between more than one tenderer without assigning any reason thereof.

- (1) Any conditional tender will not be entertained and will be rejected.
- (2) Any approved Govt. contractor or register vendor having experienced to carry out such type of work Will eligible in technical process of tender. The party has to carried out building construction work in single order of minimum Rs. 2.0 lac and if found incompetent will be out rightly rejected
- (3) The tender document will be issued & to be submitted by speed post or hand to hand at Umarsar Admn office,taluka-Lakhpat,Dist- Kutch in above date of submission.
- (4) The rate quoted by party shall excluding all applicable taxes. The party has to submit copy of PAN Card, GST certificate alongwith letter pad

Sign and sealed of  
Contractor

  
Prepared by

For G.M.D.C Ltd.  
  
General Manager (P)  
Umarsar Lignite mine


**Annexure-(A)**

**Name of Work-** -: Renovation of existing old time office bldg at Umarsar Lignite mines,  
taluka- Lakhpat, Dist- Kutch

Sr No	Item Description	Qty	Rate	Per	Amount
1	Dismantling doors, windows, ventilators etc (Wood or steel) shutters including chowkhats, architraves, holdfasts and other attachment etc complete and stacking them within all lead and lif (i) Not exceeding 3.00 sq.mt area	9		Nos	
2	Demolition of brick work and stone masoary including stacking of serviceable materials and disposal of unserviceable material with al lead and lift (i) In cement mortar	1.8		Smt	
3	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift	105.64		Smt	
4	P & L 24" x 24" vitrified 8mm thick tile flooring over 20mm (average) base of cement mortar 1:6 on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finishing withh flush pointing and cleaning the surface etc complete for Antiskid	105.64		Smt	
5	Providing and fixing extruded aluminium window having extruded aluminium color anodized section frame main outer size 127mm x 38.10mm x 1.35mm(of Jindal section no:2443, @ wt-1.384 kg/mt), horizontal four track member size 122.20mm x 31.75mm x 1.1 cm(of Jindal section :8787@wt-1.205 kg/mt),vertical member of size 122.20mm x31.75mm x 1.50mm(of Jindal section no :8935 @ wt- 1.398 kg/mt) with sliding shutter of horizontal member of size 40mm x 18mm x 1.29mm(of Jindal section no :8949 @ wt- of 0.456 kg/mt), vertical member of size 40mm x 18mm x 1.29mm(of Jindal section no :8947 @ wt- of 0.456 kg/mt, 8948 @ Wt- 0.457 kg/mt) with 5mm thk transperent bronze color tinted float glass with powder coated aluminium fittings and fixtures and transperent silicon sealant glass fixing to frame as per details etc complete for window	21.98		Smt	

Sign and sealed of  
Contractor

  
Prepared by

For G.M.D.C Ltd.  
  
General Manager (P)  
Umarsar Lignite mine

Sl. No	Item Description	Qty	Rate	Per	Amount
6	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on wall surface to give an even shade over and including priming coat with alkali resistance primer of approved brand after thoroughly brushing the surface and foreign matter also including preparing the surface even and sand papered smooth	450		Smt	
7	Providing and fixing PVC plain color false ceiling with flush type with aluminium frame	73.48		Smt	
8	Providing and fixing aluminium partly panled partly glazed door of 62.50 x 38.50 mm size section frame of 1.00 kg/mt weight with 5 mm thk plain glass selected quality and both side laminated plywood sheets with shutter frame style size 44.5mm x 44.5mm of 1.30 kg/mt wt with glazing patti rubber packing including brass pivot hinges, handles with locking arrangements etc comp with anodized fixtures and fastenings (Area up to 3.0 sq.mt)	12		Smt	

**Total Amount:-**

(In Words Rs.....)

Sign and sealed of  
Contractor

  
Prepared by

For G.M.D.C Ltd.

  
General Manager (P)  
Umarsar Lignite mine