

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: T-No-17/LP/ MISCELLANEOUS CIVIL WORKS/2023-Miscellaneous civil work for existing structure of Alstom quarters at GMDC Lignite project Panandhro, Tal: Lakhpat, Dist- Kutchh .					
PRICE BID					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(A)Loose or soft soil	268.00	CMT	0.00	0.00
2	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. Thickness including watering, ramming and consolidating etc. complete.	204.00	CMT	0.00	0.00
3	Providing and laying CC 1:3:6 (1 cement:3 coarse sand :6 crushed stone aggregate) for foundation & plinth with metal or hand broken stone of size 20mm as coarse aggregate including cost of form work, including mixing watering, ramming, consolidation, curing etc. complete, including all required machineries, tools, tackales, men pwer, labour as Elc.	148.00	CMT	0.00	0.00
4	Precast concrete block masonry (including quoin blocks jamb blocks closer etc.) with solid concrete blocks of approved size made of cement concrete 1:3:6 mix (1-Cement : 3 coarse sand: 6- graded stone aggregates of 20 mm and down grade) in foundation and plinth cement mortar 1:6 including all required material , labour ,tools , tackles, mobilization, transportaion , taxes etc. complete as per instruction of EIC.	54.00	CMT	0.00	0.00
5	Providing and laying cement concrete work 1:2:4 (1-Cement : 2- Coarse sand : 4- graded stone aggregates 20mm nominal size) and curing complete excluding cost offormwork and reinforcement for reinforcedconcretework in (B) Slabs, landing, shelves, Balconis ,Lintels,Beams, Girders and Cantilever upto floor two level.including mixing in mixer machine, necessary form work , ramming watering & finishing the honey combed surface if any scaffolding, including all requied men power,machineries, tools and tackles etc. complete as directed by EIC	38.00	CMT	0.00	0.00
6	Providing and laying TMT bar FE 415 steel reinforcement for RCC work in position including cutting,. Bending, hooking & binding the reinforcement with approved quality of binding wire etc. complete as per drawing and up to floor two level. (NO extra payment for providing chairs and supports etc. will be made)	1580.00	KG	0.00	0.00

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: T-No-17/LP/ MISCELLANEOUS CIVIL WORKS/2023-Miscellaneous civil work for existing structure of Alstom quarters at GMDC Lignite project Panandhro, Tal: Lakhpat, Dist- Kutchh .					
PRICE BID					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7	Providing and laying 15 mm thick cement plaster with Cement Mortar in proportion 1:4 (1 cement: 4 Fine sand) in single coat on brick/ concrete walls for interior plastering up to floor two levels above ground level , including normal patta , grooves , roughing the RCC surface , including necessary scaffolding , curing etc. complete as directed and specified .	430.00	SMT	0.00	0.00
8	Finishing wall with water proofing cement paint of on wall surfaces (Two coats) to give an approved brand and manufacture and of required shape even shade after thoroughly brushing the surface to remove all dirt and remains of loose powered materials incl. all matetial, labour, tools , tackles , safety measures, etc. complete as dircetd by EIC..	695.00	SMT	0.00	0.00
9	Grouting and sealing of cracks in masonry plaster slab, floor and any RCC with standard approved binding materials of pidilite or sikka or fairmate or equivalent specification and make including opening the bracks , making 'V' shape, cleaning, scaffolding and finishing the surface good as directed by EIC.	100	RMT	0.00	0.00
10	Providing and fixing chain link fencing with M.S. Angle posts 50 mm. X 50 mm. X 6 mm. And oil painting 3 coats fixed at 2.00 mt.c/c G.I. chainlink Jali strained 50 x 50mm & 10 guage and fixed to posts with MS flat 50 x 6 mm with nut & bolts, including fixing posts in ground with 0.5m x 0.5m block in C.C.1:3:6 etc. complete.	380	SMT	0.00	0.00
11	Providing and fixing pre-cast Rubber Dye / steel Dyeinter locking concrete block 60mm thick with grade ofconcrete M300 pnumatic compressed / vibratedmechanically and as per approved design Confirming toS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level asper guidlines of IRC : SP 63 2018 etc. Complete.	1088	SMT	0.00	0.00
12	Providing & fixing rolling M S gate as per the drg-given by engg. In -charge , including M S welding in built up section fixing in position and applying a prie coat of red oxide and two coat of oil paint, having locking arrangement on both side side of gate 4.00 x 1.45 mtr.weighing 220 kg/no.for 3nos. of gate including all required material , labour ,tools , tackles, mobilization, transportaion , taxes etc. complete as per instruction of EIC.	660	KG	0.00	0.00

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: T-No-17/LP/ MISCELLANEOUS CIVIL WORKS/2023-Miscellaneous civil work for existing structure of Alstom quarters at GMDC Lignite project Panandhro, Tal: Lakhpat, Dist- Kutchh .					
PRICE BID					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
13	Providng and fixing Precast RCC cover having size 0.8 mt x 0.45 mt including fixing as per site requirement smooth finishing including all required material , labour ,tools , tackles, mobilization, transportaion , taxes etc. complete as per instruction of EIC.	94	SMT	0.00	0.00
	Total				