

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: CONSTRUCTION OF STORE ROOM FOR ELECTRIC DEPTT.AT LIGNITE PROJECT TADEKSHWAR					
PRICE BID					
T-NO-15-LT-ELECTRIC STORE ROOM-2023(3 rd ATTEMPT)					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(C) Hard Murrum	36.00	CMT	0.00	0.00
2	Providing and laying P.C.C. 1:4:8(1 cement:4coarse sand:8 hand broken stone aggregate of 40 mm nominal size) for foundation and plinth with metal or hand broken stone of size 40 mm to 60 mm as coarse aggregate including mixing, watering, ramming, consolidating, curing etc. complete, including all required machineries, tools, tackles , men power , labour as directed by E.I.C.	10.50	CMT	0.00	0.00
3	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete	5.90	CMT	0.00	0.00
4	Providing and laying controlled cement concrete M.200 exposed work with curing etc. complete including the cost of formwork but excluding the cost of reinforcement for R.C.C. work in (B) COLUMNS: (i) Having cross-sectional area 0.05 to 0.08 Sq.M	3.00	CMT	0.00	0.00
5	Providing and laying controlled cement concrete M.200 exposed work with curing etc.complete including the cost of formwork but excluding the cost of reinforcement for R.C.C.workin (A) BEAMS:(iii) Having cross-sectional area more than 0.12Sq.M and upto 0.18 Sq.M	7.00	CMT	0.00	0.00
6	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete workin (C)Slabs, landing, shelves,Balconies Lintels,Beams,Girdersand Cantilever up to floor two level	28.50	CMT	0.00	0.00
7	Providing and laying controlled cement concrete M.200 exposed work with curing etc. complete including the cost of formwork but excluding the cost of reinforcement for R.C.C. work in (A) BEAMS: (i) Having cross-sectional area 0.05 to 0.08 Sq.M	3.00	CMT	0.00	0.00
8	Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering.	19.30	CMT	0.00	0.00
9	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete	10.00	CMT	0.00	0.00
10	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. Thickness including watering, ramming and consolidating etc. complete.	41.00	CMT	0.00	0.00
11	Providing formwork of ordinary timber planking so as to give a rough finish including centering shuttering strutting and propping etc. height of propping and centering below supporting floor to ceiling not exceeding 4M. and removal of the same for insitu reinforced concrete and plain concrete work in.(G) Columns Pillars Posts and struts.(1)Square Rectangular Polygonal in plan.	191.50	SMT	0.00	0.00

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: CONSTRUCTION OF STORE ROOM FOR ELECTRIC DEPTT.AT LIGNITE PROJECT TADEKSHWAR					
PRICE BID					
T-NO-15-LT-ELECTRIC STORE ROOM-2023(3 rd ATTEMPT)					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
12	Providing and laying brick masonry work using common burnt clay building bricks having crushing strength not less than 35 Kg/Cm2 in foundation and plinth , in concrete mortar 1:5 (1 cement: 5 sand) including required labour, men power, scaffolding , curing etc complete and as directed by Engineer in charge .	26.00	CMT	0.00	0.00
13	Providing, cutting, placing of TMT Bar FE 415, reinforcement steel of all diameter confirming relevant IS for RCC work , including bending , binding with 18 gauge enameled wire and placing in position complete up to any height, including providing of all laps and charirs etc. complete and as directed including all tools, tackles, safety measures , labors , materials , machinaries , transportain , mobilisation , de mobilisation etc. complete as directed by EIC	4487.00	KG	0.00	0.00
14	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor two level and finished even and smooth in (ii) Cement mortar 1:4 (1-cement :4- sand)	123.00	SMT	0.00	0.00
15	Providing and laying 15 mm thick cement plaster with Cement Mortar in proportion 1:4 (1 cement: 4 Fine sand) in single coat on brick/ concrete walls for interior plastering up to floor two levels above ground level , including normal patta , grooves , roughing the RCC surface , including necessary scaffolding , curing etc. complete as directed and specified .	110.00	SMT	0.00	0.00
16	20mm thick sand faced cement plaster on walls upto height 10 metres above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of C.M. 1:1 (1-cement : 1-sand) etc. complete.including making grooves in plaster, curing, scaffolding etc. complete including all men power, labour, tools and tackles etc. complete and as directed by EIngineer in charge .	108.00	SMT	0.00	0.00
17	Applying two coats of putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including all men power, labour, tools and tackles etc. complete and as directed by EIngineer in charge .	233.50	SMT	0.00	0.00
18	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including throughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.	233.50	SMT	0.00	0.00
19	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials.etc complete	108.00	SMT	0.00	0.00
20	Providing and laying polished Kotastones lab flooring over 20 mm (Average) thick base of cement mortar1:6 (1-cement:6-coarse sand) or L.M.1.1.5 (1-Limeputty:1.5-coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete.(A) 25mm thick	55.00	SMT	0.00	0.00

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: CONSTRUCTION OF STORE ROOM FOR ELECTRIC DEPTT.AT LIGNITE PROJECT TADEKSHWAR					
PRICE BID					
T-NO-15-LT-ELECTRIC STORE ROOM-2023(3 rd ATTEMPT)					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
21	Providing and laying polished kota stone slab 25 mm thick in risers of steps, skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1-Cement:3 coarses and) and jointed with gray cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete.	6.60	SMT	0.00	0.00
22	Providing and Laying Granite stone of 20 mm thick For Riser of steps, Dado, on Pillars, Sill/ jamb of Doors and windows with moulding edges and polishing etc complete, laid 10 mm thick cement mortar 1:3 (1-cement:3-coarses and) and jointed with grey cement Slurry including rubbing and polishing etc complete at all level including al tools, tackles, materials, labours, transportation, mobilization, demobilisation, wastages etc. complete as directed by EIC. -For Time Office building	7.00	SMT	0.00	0.00
23	Providing and fixing 35 mm thick panelled, glazed or panelled and glazed shutters, for Doors windows and clear story windows including anodised alluminium But hinges with necessary screws and indian teak wood shutters with. (C) Hard board panels.	1.90	SMT	0.00	0.00
24	CHINA-MOSAIC Providing and laying white broken china mosaic tiled flooring of broken tiles of size not more than 20 mm. x 20 mm. in cement mortar screed (1:2) well temped with wooden mallet and all joints filled with neat white cement slurry mixed with water proofing compound complete to be provided on water proofed terrace floor and fillet (vata) etc. complete as directed by Engineer incharge.	59.50	SMT	0.00	0.00
25	Providing and fixing window having extruded aluminum Colour anodized section frame main outer size 63.50 x 38.10 x 1.95mm (of Jindal Section no: 4605, @Wt1.094Kg/Rmt), horizontal two track member size 61.85mm x 31.75mm x 1.20mm (of Jindal Section no: 8687@ wt.of 0.695Kg/mt), vertical member of size 61.85mm x 31.75mm x 1.30 mm (of Jindal Section no: 8758@ wt.of 0.0.659Kg/mt) with sliding shutters of horizontal member size 40mm x 18mm x 1.29 mm (of Jindal Section no:8949@wt.of.0.456Kg/mt), vertical member of size 40mm x 18mm x 1.29mm (of Jindal Section no:8947@wt.of 0.456Kg/mt/Section8948,@Wt.0.457Kg/mt) with 5mm thick transparent bronze colour tinted float glass with powder coated aluminum fittings and fixtures and transparent silicon sealant glassixing to frame as per detail set ccomplete for window	7.20	SMT	0.00	0.00
26	Providing and fixing M.S. grills of required pattern to wooden frames of windows etc. with M.S. Flats at required spacings and frame alround, square or round bars with round headed bolts and nuts or by screws (A) Plain Grill.	180.00	KG	0.00	0.00
27	Providing and fixing rolling shutters of approved make made of 80mm wide M.S.lathsinter-locked together through their entire length and jointed together at the ends byend locks mounted on specially designed pipe shaft with bracket plates, guide channels and arragements for inside and outside locking with push-pull operation including the cost of hood cover and spring etc. complete. (A) Shutters having width below 3.5 M.	5.10	SMT	0.00	0.00

GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED					
SUB: CONSTRUCTION OF STORE ROOM FOR ELECTRIC DEPTT.AT LIGNITE PROJECT TADEKSHWAR					
PRICE BID					
T-NO-15-LT-ELECTRIC STORE ROOM-2023(3 rd ATTEMPT)					
SR NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
28	Providing and fixing to wall ceiling and floor 10.0Kg.F/Cm2 working pressure poluthene pipes of the following outside Dia. Lowdensidy, complete with special falnge compression type fittings, wall clips etc. including making good the wall ceiling and floor. (G)110 mm	40.50	RMT	0.00	0.00
29	Providing and fixing standared extruded of alluminium section of size 63.50x38.10x1.95mm@Wt1.094Kg/Rmt with colour anodized alluminium frame with 5mm thick transparent bronze colour tinted float glass with colour anodized alluminium frame for ventilation with 5mm thick frosted glass as details etc complete for.partition includng door.	9.50	SMT	0.00	0.00
	Total				